


GENERAL ABSTRACT

Name of work :- Lift Irrigation Scheme at SRSP Dam to feed Laxmi Canal - SRI RAMA SAGAR PROJECT.

S/N	Description of item.	Qty	Rate	Per	Amount
1	Land Acquisition	1	100000.00		100000
	CIVIL WORKS				
2	Approch channel		(as per Detailed Estimate)		7962559
3	Construction of Jack well and Pump House		(as per Detailed Estimate)		46369013
4	Construction of Cistern		(as per Detailed Estimate)		7781050
5	Approach Road Bridge in R.C.C from earth dam to pump House		(as per Detailed Estimate)		15726774
	MECHANICAL and ELECTRICAL WORKS				
6	Supplying & Fixation of V.T pumps with 4720LPS he6m. Col Aly I - 23M with 460kv 6.6kv 470RPM Sq C.I Motors, 33KV 6 pole 33kv 400A, 350MVA panel board, 2005kva transformer and 63kva off load transfer M.S delivery pipe 1400dia 19mm th And 30T capacity crane lighting arrangements and all accessories. as per quotation. (4 Nos pumps)	4 nos	(as per Quotation)		147711870
7	Provision for falling shutter / Nuri Return arrangement at Laxmi canal Head Regulator				224833
8	zero velocity chambers		(as per Detailed Estimate)		574106
9	Approach C.C Road for sub station yard		(as per Detailed Estimate)		3618860
10	Fencing of sub-station yard & all round Side drains		(as per Detailed Estimate)		74857
11	Bore well and supplying & fixing of submersible Bore of 5 H.P with all accessories		(as per Detailed Estimate)		49140
12	Supplying & Fixing of trashrack as per design including accessories and stoplog gate arrangements etc.		(as per Detailed Estimate)		1562750
13	Provision for Split Air conditioning system of 21 Capacity and Ventilation System for control room, office room & computer room	3.00 nos	35000	each	105000
14	I.S provision for Miscellaneous & other unforeseen works such as Water supply system, Ladders in jack well and lighting system along the approach road etc. and plantation				200000
Internal Bench Mark (I.B.M) = Rs.					232040972


 Superintending Engineer
 GVC No.1, SRS Project.
 S/S
 5/6